

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23200-00-00
Spot: N2S2S2NW Sec/Twnshp/Rge: 12-33S-11W
2230 feet from N Section Line, 1320 feet from W Section Line
Lease Name: DAVIS A Well #: 1
County: BARBER Total Vertical Depth: 5000 feet

Operator License No.: 33168
Op Name: WOOLSEY OPERATING COMPANY, LL
Address: 125 N MARKET STE 1000
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	10.75	209		WITH 200 SX CMT
PROD	4.5	4923	3500	WITH 190 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/25/2011 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 200# HULLS & 25 SX CMT. PLUG AT 600' WITH 15 SX GEL & 50 SX CMT. PLUG AT 240' WITH 75 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 02/25/2011 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMPED DOWN 4 1/2" CASING WITH 200# HULLS & 25 SX CMT. TAG TOC @ 4367'.
1ST PLUG AT 600' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 240' WITH 75 SX
CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4500	4534		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

District: 01

RECEIVED
FEB 28 2011
KCC DODGE CITY

Signed Ken Jehlik
(TECHNICIAN)

RECEIVED
MAR 10 2011
KCC WICHITA

Form CP 2/3
3/18