

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21265-00-00
Spot: NWNENW Sec/Twnshp/Rge: 3-18S-13W
4850 feet from S Section Line, 3630 feet from E Section Line
Lease Name: LUDWIG Well #: 1
County: BARTON Total Vertical Depth: 3370 feet

Operator License No.: 30705
Op Name: YOUNGER ENERGY COMPANY
Address: 453 S WEBB RD STE 100
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3210		
CIBP		3285		
CIBP		3354		
SURF	8.625	495	0	300 SX
PROD	5.5	3358	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2011 9:00 AM
Plug Co. License No.: 34044 Plug Co. Name: JD'S WELL SERVICE INC.
Proposal Rcvd. from: LUKE DYKES Company: YOUNGER ENERGY COMPANY Phone: (620) 793-2290

Proposed Plugging Method: Ordereed 400 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/28/2011 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 775' - 450'.
Ran tubing to 3270 - pumped 13 sxs gel - followed with 50 sxs cement and 100# hulls.
Pulled tubing to 1410' - pumped 75 sxs cement with 100# hulls.
Pulled tubing to 775' - circulated cement to surface with 70 sxs cement.
Pulled tubing - tied to casing and pumped 70 sxs cement.
Max. P.S.I. 300#. S.I.P. 150#.
Tied to surface pipe - pressured up to 300# P.S.I. - would not take cement.

Perfs:

Top	Bot	Thru	Comments
3345	3351		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie

(TECHNICIAN) RECEIVED

CM

MAR 04 2011

Form CP-2/3

KCC WICHITA

7/18

MAR 02 2011