

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-23624-00-00
Spot: E2SESWNE Sec/Twnshp/Rge: 26-25S-11W
2285 feet from N Section Line, 1469 feet from E Section Line
Lease Name: ZINK A Well #: 1
County: STAFFORD Total Vertical Depth: 4400 feet

Operator License No.: 31980
Op Name: LOTUS OPERATING COMPANY, L.L.C.
Address: 100 S MAIN STE 420
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3950		WITH 2 SX CMT
SURF	10.75	257		WITH 250 SX CMT
	11	8.625	1091	WITH 300 SX CMT
PROD	5.5	4262	2204	WITH 200 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/21/2011 9:00 AM
Plug Co. License No.: 33939 Plug Co. Name: BLACKGOLD OILFIELD SERVICE LLC
Proposal Revd. from: ROBIN BROWN Company: LOTUS OPERATING Phone: (620) 546-4801

Proposed Plugging Method: SET CIBP @ 3950' & 2 SX CMT. PRESSURE 10 3/4" X 8 5/8" ANNULUS TO 500 PSIG WITH CMT. PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. PLUG AT 290' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/21/2011 1:52 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3950' WITH 2 SX CMT ON TOP WITH DUMP BAILER. PUMPED 150 SX CMT DOWN THE 10 3/4" X 8 5/8" ANNULUS. MAXIMUM PRESSURE 350 PSIG. INITIAL SHUT IN PRESSURE 200 PSIG. 1ST PLUG AT 1120' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 290' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4002	4028		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED
FEB 28 2011
KCC DODGE CITY

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
MAR 10 2011
KCC WICHITA

Form OP-2/3
3/18