

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-02148-00-01
Spot: NWNWSE Sec/Twnshp/Rge: 29-14S-12W
2310 feet from S Section Line, 2310 feet from E Section Line
Lease Name: KEPKA HEIM Well #: 1
County: RUSSELL Total Vertical Depth: 3152 feet

Operator License No.: 31522

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	280	0	200 SXS
PROD	5.5	3152	0	400 SXS

Op Name: MICHAELIS, GERALD DBA GERALD MI

Address: 979 NW 230TH RD
RUSSELL, KS 67665

Well Type: EOR

UIC Docket No: E15865.1

Date/Time to Plug: 02/24/2011 1:30 PM

Plug Co. License No.: 6123

Plug Co. Name: CHASE WELL SERVICE, INC.

Proposal Rcvd. from: GERALD MICHAELIS

Company: GERALD MICHAELIS OIL

Phone: (620) 935-4230

Proposed Ordered 280 sxs 60/40 pozmix - 4% gel - 300# hulls - 7 sxs gel.

Plugging PBTD 2866'. Perf: 250' - 600' - 1200'.

Method:

Plugging Proposal Received By: RAY DINKEL

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/24/2011 6:30 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

02/24/2011 - Ran tubing to 2750' - pumped 7 sxs gel - followed with 75 sxs cement with 100# hulls.

Pulled tubing to 1300' - pumped 75 sxs cement with 100# hulls.

Pulled tubing to 550' - pumped 80 sxs cement with 100# hulls - cement circulated.

POOH. Hooked up to casing and pumped 15 sxs cement.

Max. P.S.I. 350#. S.I.P. 300#.

03/02/2011 - Casing was cut off. Fluid down 80' in surface pipe and 40' in 5 1/2" casing.

Topped off with approximately 3/4 to 1 yard of class "A" cement ready mix.

RECEIVED

MAR 08 2011

KCC WICHITA

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4760.

Plugged through: TBG

District: 04

Signed Ray A. Dinkel
(TECHNICIAN) CM

Form CP-2/3

3/18

MAR 03 2011