

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-00431-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 5-31S-32W
2790 feet from S Section Line, 2520 feet from E Section Line
Lease Name: PYLE GAS UNIT B Well #: 1
County: SEWARD Total Vertical Depth: 2704 feet

Operator License No.: 33127
Op Name: CHAPARRAL ENERGY, L.L.C.
Address: 701 CEDAR LK BLVD
OKLAHOMA CITY, OK 73114

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	621		WITH 400 SX CMT
PROD	5.5	2667	0	WITH 800 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/07/2011 11:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Rcvd. from: JOEL Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PUMP HULLS & 125 SX CMT. LET STE 2 HOURS & TAG CMT. FILL 5 1/2" TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACCLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/07/2011 4:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 5 1/2" CASING WITH CMT FROM 2704' TO 0' USING 300 SX CLASS C & 2% GEL WITH 400# HULLS & 4% CC IN THE FIRST 140 SX CMT IN 2 STAGES. FILL ANNULUS WITH 30 SX CMT. STAYED FULL.

Perfs:


Top	Bot	Thru	Comments
2667	2704	OH	KIDER
2648	2650		HERRINGTON
2633	2644		HERRINGTON
2626	2629		HERRINGTON

Remarks: USED CLASS C & 2% GEL BY ORR ENTERPRISES.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

RECEIVED
FEB 14 2011
KCC DODGE CITY

RECEIVED
MAR 01 2011
KCC WICHITA

