

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-185-33604-00-01
Spot: SWNENE Sec/Twnshp/Rge: 5-25S-13W
4314 feet from S Section Line, 1011 feet from E Section Line
Lease Name: GLASSCOCK Well #: 4-1
County: STAFFORD Total Vertical Depth: 4286 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3730		WITH 2 SX CMT
SURF	8.625	252		WITH 225 SX CMT
PROD	4.5	4000	2030	WITH 250 SX CMT

Well Type: EOR UIC Docket No: E14551.1 Date/Time to Plug: 02/21/2011 9:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/21/2011 11:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3730' & PUT 2 SX CMT ON TOP OF CIBP. 1ST PLUG AT 830' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 280' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3894	3901		LKC
3860	3866		LKC
3823	3838		LKC
3817	3823		LKC
3786	3792		LKC

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

KCC WICHITA

RECEIVED

MAR - 1 2011

KCC DODGE CITY

RECEIVED

MAR 10 2011

Form CP 2/3

3/18