

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21132-00-00
Spot: SWNE Sec/Twnshp/Rge: 8-24S-8W
4360 feet from S Section Line, 1133 feet from E Section Line
Lease Name: FARNEY Well #: 3
County: RENO Total Vertical Depth: 4165 feet

Operator License No.: 5585
Op Name: CLINTON PRODUCTION, INC.
Address: 330 N ARMOUR
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	283		
PROD	4.5	4164	2038	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2011 9:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKES TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

RECEIVED
MAR 11 2011
KCC WICHITA

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL
Date/Time Plugging Completed: 02/28/2011 11:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND PERFS TO 3500' AND CAP WITH 4 SX'S CEMENT. CUT CASING OFF AT 2038' AND PULL TO 1350' AND PUMP 35 SX'S CEMENT. PULL CASING TO 750' AND PUMP 35 SX'S CEMENT. PULL CASING TO 325' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3600	3621	CSG	

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-37543.

Plugged through: CSG

District: 02

Signed Virgil Clothier
(TECHNICIAN)