

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21172-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 19-18S-9W
2963 feet from S Section Line, 4950 feet from E Section Line
Lease Name: BOLDT A Well #: 3
County: RICE Total Vertical Depth: 3230 feet

Operator License No.: 3682
Op Name: CONNELL, MARK ALLEN
Address: 606 W ALBRO ST
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	256		150 SX
T1	2.375	3218	1319	
PROD	4.5	3230		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/08/2011 11:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE, INC. Phone: (620) 938-2943

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL
Date/Time Plugging Completed: 03/08/2011 3:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU. TUBING BROKE OFF AT SURFACE. CUT OFF WELL HEAD AND WELD COLLAR ON TUBING. ATTEMPTED TO PULL TUBING -- COULD NOT GET TUBING FREE. AFTER 2 FAILED ATTEMPTS TO SHOOT OFF TUBING AT 2000' AND 1790', DID FINALLY GET TUBING SHOT OFF AT 1319'. PULL TUBING ON OUT. PERFORATE AT 1200', 850', AND 310'. RUN TUBING DOWN TO 1300' AND PUMP 50 SX'S COMMON CEMENT. PULL TUBING UP TO 850' AND WAIT APPROX 1 HR. TAGGED CEMENT AT 1150'. PUMPED 35 SX'S CEMENT AT 850'. PULL TUBING TO 310' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3225	3230	CSG	CASING

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-36180. LOG TECH OF KS #6428.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED
MAR 14 2011
KCC WICHITA

✓ 3/18

✓ JK