

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-20880-00-01
Spot: SWNESE Sec/Twnshp/Rge: 9-12S-21W
2299 feet from S Section Line, 397 feet from E Section Line
Lease Name: MUSGRAVE Well #: 9-9
County: TREGO Total Vertical Depth: 4181 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	296	0	200 sxs cement
L1	4.5	4109	0	125 sxs cement
PROD	5.5	4166	0	w/250 sxs cement

Well Type: SWD UIC Docket No: D25423.0 Date/Time to Plug: 03/10/2011 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GEORGE STOPPELWERTH Company: DARRAH, JOHN JAY, JR. Phone: (620) 786-4046

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 600# hulls.
Junk in the hole. PC at 1820' w/500 sxs. PBTB 3990'.
Well originally known as Musgrave #9-10

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/10/2011 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service RIH with tubing to 2950'.
Swift Cementing rigged to tubing and mixed and pumped 50 sxs neat - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 1450'. Swift rigged to tubing and mixed and pumped 115 sxs cement with 300# hulls mixed in to circulate cement to surface.
Pulled tubing - rigged to 4 1/2" casing with a swedge and pumped 20 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.
Rigged to 8 5/8" and pumped 65 sxs cement.
Max. P.S.I. 150#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
4050	4120		Arbuckle


RECEIVED
MAR 16 2011
KCC WICHITA

Remarks: SWIFT CEMENTING COMPANY-TICKET #19544.

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

✓ 3/18

MAR 11 2011