

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20397-00-02
Spot: NWNENE Sec/Twnshp/Rge: 26-20S-14W
4950 feet from S Section Line, 990 feet from E Section Line
Lease Name: CHISHOLM OWWO Well #: 1-26
County: BARTON Total Vertical Depth: 3564 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	808	0	475 SX
PROD	4.5	2434	0	150 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/18/2011 10:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D.S & W WELL SERVICING, INC.
Proposal Rcvd. from: ROB LONG Company: F.G. HOLL COMPANY L.L.C. Phone: (316) 684-8481

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls.
Shallow gas well. CIBP set at 2130'.

Plugging Proposal Received By: BRUCE BASYE Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/18/2011 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 750'.
Ran tubing to 2090' - pumped 100 sxs cement with 100# hulls.
Pulled tubing to 800' - circulated to surface with 75 sxs cement.
Pulled tubing - tied to casing - circulated cement out surface pipe with 125 sxs cement.

Perfs:

Top	Bot	Thru	Comments
1988	1992		
1801	1812		
1756	1762		

Remarks: BASIC WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed

Bruce Rodie

(TECHNICIAN)

RECEIVED

MAR 03 2011^{orm CP-2/3}

KCC WICHITA *3/18*

FEB 23 2011