

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-115-20486-00-00  
Spot: NWNWSENE Sec/Twnshp/Rge: 27-22S-4E  
3956 feet from S Section Line, 1312 feet from E Section Line  
Lease Name: JENSEN Well #: 5  
County: MARION Total Vertical Depth: 2509 feet

Operator License No.: 5610  
Op Name: BRUCE OIL COMPANY, L.L.C.  
Address: 1704 LIMESTONE RD  
MCPHERSON, KS 67460

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 165        |             | 75 SX    |
| PROD   | 5.5   | 2521       | 580         | 50 SX    |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: LEVI KOEHN Company: \_\_\_\_\_ Phone: (620) 241-2938

Proposed Plugging Method: BAIL MUD DOWN TO WITHIN 50' OF PERFORATIONS. THEN SAND OFF AND CAP WITH 6 SXS. PULL AT LEAST 300' OF CASING AND BUILD A BRIDGE AND CEMENT TO SURFACE.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/01/2010 3:55 PM KCC Agent: SHANE JONES

Actual Plugging Report:

8/27/2010 SUNFLOWER WELL SERVICE STRIPED WELL AND DROPPED SAND.  
8/31/2010 SUNFLOWER TAGGED SAND @2377' AND CAPPED IT WITH 6 SXS CEMENT. THEY TRIED RIPPING CASING @ 1000'. THEY ENDED UP PULLING WELDED COLLAR OFF CASING. BUD CALLED SAID IT WOULD BE TO LATE BY THE TIME WELDER GETS OUT TO DO TOP PLUG TODAY. 9/1/2010 I ARRIVED ON LOCATION. SUNFLOWER STILL TRYING TO RIP CASING. AT 10:00 AM GOT CASING FREED AND STARTED PULLING. THEY RETRIEVED APPROX 580' OF 5.5" CASING THEY BAILED FLUID DOWN TO APPROX 300'. THEY USED 6YDS OF SLURRY FROM HILLSBORO REDIMIX TO DUE THE TOP PLUG. 9/2/2010 BUD CALLED AND SAID PLUG WAS STILL AT SURFACE. COULD HE GO AHEAD AND BACKFILL.

Perfs:

| Top  | Bot  | Thru | Comments    |
|------|------|------|-------------|
| 2436 | 2447 | CSG  | MISSISSIPPI |
| 2427 | 2430 | CSG  | MISSISSIPPI |

10/14/11  
2011060103

Remarks:

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

RECEIVED  
SEP 15 2010 2/3  
KCC WICHITA

136