

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-141-20411-00-00
Spot: SENWNWSW Sec/Twnshp/Rge: 9-10S-12W
2090 feet from S Section Line, 430 feet from W Section Line
Lease Name: HIRST A Well #: 1
County: OSBORNE Total Vertical Depth: 4050 feet

Operator License No.: 3956
Op Name: BRUNGARDT OIL AND LEASING INC.
Address: 529 E 14TH PO BOX 871
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	219		

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/10/2010 11:00 AM
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC
Proposal Rcvd. from: TOM ENGEL Company: BRUNGARDT OIL AND LEASING I Phone: (785) 483-4975

Proposed Plugging Method: Ordered 230 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE
Date/Time Plugging Completed: 08/10/2010 12:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st. Plug at 3985' w/25 sxs.
2nd. Plug at 970' w/25 sxs.
3rd. Plug at 690' w/100 sxs.
4th. Plug at 250' w/40 sxs.
5th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

10/14/10
2011060104

RECEIVED
AUG 23 2010

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed



(TECHNICIAN)

CM

Form CP-2/3

AUG 13 2010