

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-141-20410-00-00
Spot: SENE SWNE Sec/Twnshp/Rge: 32-9S-12W
1700 feet from N Section Line, 1490 feet from E Section Line
Lease Name: KENDIG A Well #: 1
County: OSBORNE Total Vertical Depth: 3297 feet

Operator License No.: 3956
Op Name: BRUNGARDT OIL AND LEASING INC.
Address: 529 E 14TH PO BOX 871
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212	0	w/165 sxs cmt
PC		1102		
PROD	5.5	3290	2464	w/165 sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/07/2010 10:00 AM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: GARY L. BRUNGARDT Company: BRUNGARDT OIL AND LEASING I Phone: (785) 483-4975

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls.
Cut casing at 2464'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 09/07/2010 5:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3230' - pumped 25 sxs cement.
Pulled tubing out and cut casing at 2464'.
Pulled casing to 1650' - pumped 125 sxs cement with 300# hulls.
Pulled casing to 1050' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 570' - pumped 60 sxs cement with 200# hulls.
Pulled casing to 200' - pumped 60 sxs cement - cement circulated.
POOH. Cellar and hole stayed full.

Perfs:

Remarks: ALLIED CEMENTING COMPANY-TICKET #41976.

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

RECEIVED

SEP 13 2010 Form CP-2/3

KCC WICHITA

SEP 08 2010