

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-23035-00-00  
Spot: NWSWNW Sec/Twnshp/Rge: 9-15S-12W  
3630 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: KAUFMAN Well #: 8  
County: RUSSELL Total Vertical Depth: 3274 feet

Operator License No.: 33633  
Op Name: CARTER, JIM DBA J CARTER OIL  
Address: PO BOX 491  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	504	0	225 SX
PROD	5.5	3265	0	125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/21/2010 1:00 PM  
Plug Co. License No.: 32528 Plug Co. Name: FUNK, DAVID A. DBA OIL AND OPERATING SERVICES  
Proposal Rcvd. from: JIM CARTER Company: J CARTER OIL Phone: (785) 483-8067

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Packer at 2582' and mud anchor left in the hole.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/21/2010 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Hooked up to casing and pumped 125 sxs cement - followed with 165 sxs cement with 450# hulls.  
Max. P.S.I. 700#. Fell off.  
Waited - re-pressured to 500# P.S.I. Held.  
Shut in well.  
Braden head was full of cement from squeeze job in 2005' by Allied.  
Casing holes from 862' - 2276'.  
Re-squeeze by Copeland at 1650' - 1675' - twice.

Perfs:

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4533.

Plugged through: CSG

10/14/11  
2011060100

RECEIVED

SEP 27 2010

KCC WICHITA

District: 04

Signed

*Ray Dinkel*

(TECHNICIAN)

CM

Form CP-2/3

SEP 24 2010