

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-25131-00-00
Spot: E2NENWNE Sec/Twnshp/Rge: 22-17S-21W
330 feet from N Section Line, 1380 feet from E Section Line
Lease Name: CONNER Well #: 1
County: NESS Total Vertical Depth: 4225 feet

Operator License No.: 9860
Op Name: CASTLE RESOURCES, INC.
Address: BOX 87
SCHOENCHEN, KS 67667

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	215		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/13/2010 2:15 AM
Plug Co. License No.: 33493 Plug Co. Name: AMERICAN EAGLE DRILLING LLC
Proposal Rcvd. from: TOBY Company: AMERICAN EAGLE DRILLING LLC Phone: (303) 722-2899

Proposed Plugging Method: 1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 75 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: NONE
Date/Time Plugging Completed: 09/13/2010 4:15 AM KCC Agent: STEVE DURRANT

Actual Plugging Report:

1ST PLUG AT 1500' WITH 50 SX CMT. 2ND PLUG AT 780' WITH 75 SX CMT. 3RD PLUG AT 240' WITH 40 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. 5TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 6TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED
SEP 22 2010
KCC DODGE CITY

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED
SEP 27 2010

KCC WICHITA

10/14/10
2010 60108