

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-22636-00-00  
Spot: S2NWSWNW Sec/Twnshp/Rge: 13-11S-25W  
3360 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: ZIEGLER/HURT Well #: 2  
County: TREGO Total Vertical Depth: 4334 feet

Operator License No.: 33269  
Op Name: CENTRAL OPERATING, INC.  
Address: 1600 BROADWAY STE 1050  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3908		
SURF	8.625	218	0	150 SX
T1	2.375	3870		
PROD	5.5	3988	0	270 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 09/14/2010 9:00 AM  
Plug Co. License No.: 4072 Plug Co. Name: PLAINS, INC  
Proposal Rcvd. from: BRETT HILDEBRAND Company: MURFIN DRILLING COMPANY, IN Phone: (785) 871-7311

Proposed Plugging Method: Ordered 325 sxs 60/40 pozmix - 4% gel - 500# hulls - 12 sxs gel.  
CIBP 3908'. PC-1938' w/140 sxs.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 09/14/2010 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Plains, Inc. RIH with tubing to 3852'.  
Allied rigged to tubing and pumped 12 sxs gel - followed with 50 sxs cement with 200# hulls mixed in.  
Pulled tubing to 2100'. Allied rigged to tubing and pumped 100 sxs cement with 200# hulls mixed in.  
Pulled tubing to 1100'. Allied rigged to tubing and mixed and pumped 85 sxs cement with 100# hulls to circulate cement to pit area.  
Pulled tubing. Topped off 5 1/2" casing with 10 sxs cement.  
Hole standing full.  
Rigged to 8 5/8" - instant pressure.  
Max. P.S.I. 600#. S.I.P. 600#.

Perfs:

Top	Bot	Thru	Comments
3920	3924		LKC
3854	3858		LKC

10/14/10  
2011060109

Remarks: ALLIED CEMENTING COMPANY-TICKET #41987.

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

(TECHNICIAN) RECEIVED

CM

SEP 20 2010 Form CP-2/3

SEP 14 2010

KCC WICHITA