

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-20305-00-02  
Spot: NESWNW Sec/Twnshp/Rge: 7-35S-14W  
3612 feet from S Section Line, 4326 feet from E Section Line  
Lease Name: DAVIS RANCH Well #: D 1  
County: BARBER Total Vertical Depth: 4900 feet

Operator License No.: 3532  
Op Name: CMX, INC.  
Address: 1700 N WATERFRONT PKWY BLDG 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4720		WITH 2 SX CMT
SURF	8.625	835		WITH 445 SX CMT
PROD	4.5	4872	2700	WITH 125 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/26/2010 9:00 AM  
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION  
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: CIBP @ 4800' WITH 2 SX CMT. PLUG AT 860' WITH 12 SX GEL & 50 SX CMT. PLUG AT 300' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/26/2010 10:15 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

\*\*UNABLE TO GET CIBP IN HOLE BELOW 4720\*\*SET CIBP @ 4720' & PUT 2 SX CMT ON TOP OF CIBP. 1ST PLUG AT 860' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4870	4900		MISSISSIPPI

10/14/11  
2011060113

RECEIVED  
SEP 20 2010

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED

SEP - 2 2010

KCC DODGE CITY