

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-125-30774-00-00  
Spot: NWNE Sec/Twnshp/Rge: 9-33S-17E  
660 feet from N Section Line, 1980 feet from E Section Line  
Lease Name: T ANDERSON Well #: 2-9  
County: MONTGOMERY Total Vertical Depth: 1003 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	21		4 SX
PROD	4.5	998		110 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/14/2010 8:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX R. ASHLOCK OR ROB Company: \_\_\_\_\_ Phone: (620) 365-3111

Proposed Plugging Method: CMT FROM TD TO 400', GEL SPACER FROM 400' TO 250', CMT FROM 250' TO SURFACE - OK'D BY RUSSELL HINE, KCC OFFICE IN CHANUTE, 7/8/10.

Plugging Proposal Received By: RUSSELL HINE Witness Type: NONE  
Date/Time Plugging Completed: 08/05/2010 5:00 PM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Ran 2" cement string to td. Pumped cement from TD to 400' Pulled pipe up to 400' and placed gel spacer from 400' to 250'. Pulled pipe to 250' and circulated cement to surface. Pulled 2" and topped off. Contractor reported 78 scaks of portland and 1-1/2 sacks of gel.

Perfs:

Top	Bot	Thru	Comments
903	906		
842	845		
713	715		
670	674		
650	654		
586	589		
538	542		
504	507		
478	482		
450	452		

RECEIVED

AUG 26 2010 RHH

KCC Chanute Dist. #3

10/14/11  
2011060114

RECEIVED

SEP 01 2010

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

*Russell Hine*

(TECHNICIAN)