

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-099-24487-00-00  
Spot: NWSWSESW Sec/Twnshp/Rge: 36-32S-17E  
400 feet from S Section Line, 1600 feet from W Section Line  
Lease Name: COPLIN Well #: 14-36  
County: LABETTE Total Vertical Depth: 1105 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1090		
SURF	8.625	20		5 SX
PROD	5.5	1090		145 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/14/2010 8:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: REX R. ASHLOCK OR ROB Company: COLT ENERGY Phone: (620) 365-3111

Proposed Plugging Method: CMT FROM TD TO 900', GEL SPACER FROM 900' TO 700', CMT FROM 700' TO 500', GEL SPACER FROM 500' TO 250' CMT FROM 250' TO SURFACE. OK'D BY RUSSELL HINES, KCC DIST 3 OFFICE IN CHANUTE.

Plugging Proposal Received By: RUSSELL HINE WitnessType: NONE  
Date/Time Plugging Completed: 08/05/2010 4:00 PM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Pulled equipment from well and 2" cement string was ran into TD. Cement was pumped from TD to 900'. Cement string was pulled to 900' and gel spacer was placed from 900' to 700'. Pipe was pulled to 700' and cement was pumped from 700' to 500'. Pipe pulled to 500' and gel spacer from 500' to 250'. Pipe pulled to 250' and cement was circulated to surface. Pipe pulled and topped off. 91 sks cement and 2 sks gel reported

Perfs:

Top	Bot	Thru	Comments
986	989		PENNSYLVANIAN
922	924		PENNSYLVANIAN
668	670		PENNSYLVANIAN
629	632		PENNSYLVANIAN
612	614		PENNSYLVANIAN
598	601		PENNSYLVANIAN
564	568		PENNSYLVANIAN
536	540		PENNSYLVANIAN

RECEIVED

SEP 02 2010

RH

KCC Chanute Dist. #3

10/14/11  
2011060114

Remarks:

Plugged through: TBG

District: 03

Signed

*Russell Hine*

(TECHNICIAN)

RECEIVED

Form CP-2/3

SEP 13 2010

KCC WICHITA