

TO: STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-031-19166-00-00
Spot: NESESESE Sec/Twnshp/Rge: 2-23S-16E
620 feet from S Section Line, 165 feet from E Section Line
Lease Name: MURRAY Well #: 2A
County: COFFEY Total Vertical Depth: 975 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	20		4 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2010 8:00 AM
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP
Proposal Rcvd. from: BUTCH NORMAN Company: _____ Phone: (620) 365-3111

Proposed Plugging Method: COMPANY UNIT WILL RUN 1" TO 445' INSIDE OF 4 1/2" AND FILL TO SURFACE WITH CEMENT. PULL 1" & THEN HOOK ONTO 4 1/2" CSG AND SQUEEZE AS MUCH CEMENT IN TO WELL AS POSSIBLE TO PRESSURE UP.

Plugging Proposal Received By: MICHAEL HEFFERN Witness Type: PARTIAL
Date/Time Plugging Completed 08/12/2010 3:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

pulled 1" & pump 2" parted fished out 9 joints ran spear in no fish ran mouse trap over 2" pulled out mouse trap ran back in with mouse trap numerous time no luck getting pipe out opted to pump into well to see if it would take fluid ran washover pipe to to 445' pumped 70 sxs cement inside of 4.5" ran 1" out side of casing pumped 62 sxs cement.

RECEIVED

AUG 30 2010 M H

KCC Chanute Dist. #3

Perfs:

Top	Bot	Thru	Comments
956	966		SQUIRREL

10/14/11
2011060114

RECEIVED

SEP 03 2010

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed Mike Heffern
(TECHNICIAN)