

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02802-00-00
Spot: SESWSW Sec/Twnshp/Rge: 4-9S-23W
330 feet from S Section Line, 4290 feet from E Section Line
Lease Name: BRUSH CREEK UNIT Well #: 106
County: GRAHAM Total Vertical Depth: 3840 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212	0	175 SX
PROD	5.5	3840	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/12/2010 10:00 AM
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE
Proposal Rcvd. from: BO DARRAH Company: DARRAH, JOHN JAY, JR. Phone: (316) 219-3390

Proposed Plugging Method: Ordered 550 sxs 60/40 pozmix - 4% gel - 600# hulls.
Perfs: 1970' - 1135' - 200'.
Tubing stuck in the hole at 3577'.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2010 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3540' - pumped 150 sxs cement with 300# hulls.
Pulled tubing to 2485' - pumped 125 sxs cement.
Pulled tubing to 1430' - pumped 150 sxs cement - good circulation of cement.
Pulled tubing out - tied onto backside and pumped 100 sxs cement.
S.I.P. 100#.
Filled 5 1/2" with 25 sxs cement - tube full.

Perfs:

Top	Bot	Thru	Comments
3660	3820		LKC

10/14/11
2011060120

RECEIVED
AUG 18 2010


Remarks: S.O.S. CEMENTING COMPANY-TICKET #458.

Plugged through: TBG

KCC WICHITA

District: 04

Signed



(TECHNICIAN)

CM

IMPERIAL OIL OF KANS

#6

McPHERSON

4-9-23W

SE SW SW

Contr. IMPERIAL OIL OF KANS

GRAHAM

County

E 23 1/4 RB Comm. 5-31-57

Comp. 7-26-57

IP 322 BOPD/KC


BOMB

Tops	Depth	Datum
ANH	1950	364
HEEB	3589	-1275
TOR	3613	-1299
LANS	3628	-1314
TD	3840	-1526

Casing
 8" 211 1755
 5" 3840 1755

DST 3648-68/1 HR, 120' G, 140' O,
 BHP 1300#
 DST 3699-3708/1 HR, 1900' G, 390' O,
 BHP 1335#
 DST 3715-28/1 HR, 425' G, 125' H OCM,
 550' OGW, BHP 1270#
 PERF 28/3796-3800: 1 GOPH: ACID 2000:
 6 BOPH/12 HRS: PERF 28/3816-20:
 21/3780-83: ACID 3000: 30 BOPH/4
 HRS

BRUSH CREEK POOL



INDEPENDENT OIL & GAS SERVICE