

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21356-00-00
Spot: SESENW Sec/Twnshp/Rge: 24-12S-22W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ZIEGLER Well #: 1
County: TREGO Total Vertical Depth: 4059 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	268	0	170 SX
PROD	5.5	4059	0	250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/24/2010 2:30 PM
Plug Co. License No.: 34410 Plug Co. Name: AMERICAN PULLING SERVICE
Proposal Rcvd. from: MIKE KERNS Company: DARRAH, JOHN JAY, JR. Phone: (785) 623-3780

Proposed: Ordered 500 sxs 60/40 pozmix - 4% gel - 500# hulls.
Plugging: Log Tech perfed at 1775' - 950' - 250'.
Method: Tubing parted at 1085' -fished tubing to 2137'.
Fished and washed for 5 days.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/24/2010 3:05 PM KCC Agent: PAT STAAB

Actual Plugging Report:

American Pulling Services RIH with tubing to 1961' - tagged - pulled one joint to 1931'.
Allied rigged to tubing and mixed and pumped 125 sxs 60/40 pozmix - 4% gel.
Pulled tubing to 1011'. Allied rigged to tubing and pumped 135 sxs cement with 300# hulls to circulate cement to pit area.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 45 sxs cement with 50# hulls. Max. P.S.I. 700#. S.I.P. 500#.
Rigged to 8 5/8" casing and pumped 10 sxs cement. Max. P..I. 600#. S.I.P. 600#.

Perfs:

Top	Bot	Thru	Comments
3982	3990		Marm
10/14/11 2011060120			

Remarks: ALLIED CEMENTING COMPANY-TICKET #36816.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

CM

RECEIVED

AUG 26 2010

Form CP-2/3

KCC WICHITA

AUG 25 2010


JOHN JAY DARRAH, JR.
 405 CENTURY PLAZA
 WICHITA, KS 67202

#1 ZIEGLER

24-12-22W
 SE SE NW

CONTR MALLARD DRILLING CO., INC. CITY TREGO

GEOLOGICAL FIELD WC (SHERFICK SOUTH DISC)



ELV 2354 KB SPD 10/17/83 CARD ISSUED 2/2/84 IP P 25 BOPD, NW
 2346 GL MARM 3982-3990

API 15-195-21,356

LOG	Tops	Depth/Datum
ANH	1773 + 581
B/ANH	1821 + 533
TOP	3380-1026
HEEB	3600-1246
TOR	3623-1269
LANS	3636-1282
BKC	3876-1522
MARM	3962-1608
ARB	4045-1691
PBTD	4018-1664
RTD	4050-1696

8 5/8 " 268/170 SX
 DST (1) 3601-3650 (TOR, LANS) / 30-45-30-45, 170' GIP, REC 134' OCM, SIP 922-901#, FP 120-120#
 DST (2) 3653-3665 (LKC) / 20-20-5-0, REC 5' M, ISIP 44#, NO FSIP, FP 44#, NO FFP#
 DST (3) 3700-17 (LKC) / 30-45-30-45, 337' GIP, REC 136' OCM, SIP 899-888#, FP 43-76#
 DST (4) 3717-30 (LKC) / 20-20-20-20, 745' GIP, REC 139' HOCM, 124' OCM, 992' WTR, SIP 1244-1169#, FP 174-586#
 MICT - CO, PF (MARM) 16/3982-3990, SWB LD, GSO, NAT, R&T, POP. P 25 BOPD, NW. 11/30/83

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS