

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-10023-00-01
Spot: W2NWSW Sec/Twnshp/Rge: 15-21S-21W
1980 feet from S Section Line, 4820 feet from E Section Line
Lease Name: HULING AB Well #: W03
County: HODGEMAN Total Vertical Depth: 4387 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1289		WITH 650 SX CMT
PROD	4.5	4356	0	WITH 100 SX CMT

Well Type: EOR UIC Docket No: E11855.1 Date/Time to Plug: 01/24/2011 10:30 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JERRY WIRTZ Company: NOBLE ENERGY Phone: (785) 639-6304

Proposed Plugging Method: TOP OF FISH @ 3757'. RUN TBG TO 3700' & PUMP 50 SX CMT MIXED WITH HULLS. PULL TBG & PERFORATE @ 1320'. RUN TBG TO 1320' & CIRCULATE CMT TO SURFACE. SHUT IN CASING & CIRCULATE 8 5/8" X 4 1/2" ANNULUS WITH CMT. REFILL CASING IF NEEDED.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/24/2011 4:05 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

TOP OF FISH @ 3757'. RAN TBG TO 3690' & PUMPED 200# HULLS & 50 SX CMT WITH 2% CC. PULLED TBG OUT OF HOLE. PERFORATED @ 1320'. RAN TBG TO 1333' & CIRCULATED CMT UP 4 1/2" WITH 50# HULLS & 120 SX CMT. PULLED TBG & TIED ONTO CASING & PUMPED 405 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4356	4387		MISSISSIPPI

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: TBG

RECEIVED

JAN 31 2011

KCC WICHITA

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED

JAN 26 2011

KCC DODGE CITY

Form CR-2/3