

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-22158-00-00
Spot: SWNENWNE Sec/Twnshp/Rge: 15-9S-21W
4780 feet from S Section Line, 1832 feet from E Section Line
Lease Name: TREXLER Well #: 16
County: GRAHAM Total Vertical Depth: 4047 feet

Operator License No.: 33190
Op Name: NOBLE ENERGY, INC.
Address: 1625 BROADWAY, STE 2200
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3645		
CIBP		3681		
SURF	10.75	1004	0	740 SX
COND	20	60		
PROD	7	4046	0	200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/04/2011 9:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: JERRY WIRTZ Company: NOBLE ENERGY, INC. Phone: (785) 639-6304

Proposed Plugging Method: Ordered out 75 sxs common - 3% c.c. - 22 sxs gel spacer - 450 sxs 60/40 pozmix - 4% gel.
Company ordered 75 sxs ceommon - 3% c.c. - 22 sxs gel - 800 sxs 60/40 pozmix - 4% gel.
Perforated two holes at 950'.
CIBP at 3645' and 3681'.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2011 7:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Sandline drilled CIBP at 3380' - knocked out to 3640'.
Ran 2 7/8" tubing to 3370'.
Basic pumped 22 sxs gel spacer - followed with 75 sxs common cement with 3% c.c.
Pulled tubing to 1648' - pumped 270 sxs cement.
Pulled to 1007' - pumped 470 sxs cement - cwc out 7" and 10 3/4".
PTOH. Topped off with 30 sxs.

Perfs:

Top	Bot	Thru	Comments
3899	3903		ARBUCKLE
3883	3887		ARBUCKLE
3755	3760		ARBUCKLE
3718	3736		ARBUCKLE
3685	3690		ARBUCKLE
3674	3679		LIME
3580	3592		LIK
3562	3566		LKC
3550	3560		LKC
3480	3484		LKC
3471	3476		LKC
3435	3444		LKC
3394	3402		LKC

Remarks: BASIC CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

RECEIVED
FEB 09 2011
KCC WICHITA

FEB 07 2011