

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-205-20814-00-01

Spot: SESWNW

Sec/Twnshp/Rge: 3-28S-17E

2861 feet from S Section Line,

4123 feet from E Section Line

Lease Name: STOVER ANDER

Well #: 2

County: WILSON

Total Vertical Depth: 1050 feet

Operator License No.: 3834

Op Name: ONYXX OIL CORPORATION

Address: 929 HIGHLAND
CHANUTE, KS 66720

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10	20		20 is estimate
PROD	2.5	1000		1000 is an estimate

Well Type: EOR

UIC Docket No: E13022.2

Date/Time to Plug: 12/03/2010 8:00 AM

Plug Co. License No.: 33749

Plug Co. Name: KEPLEY WELL SERVICE, LLC

Proposal Rcvd. from: MIKE KEPLEY

Company: KEPLEY WELL SERVICE, LLC

Phone: (620) 431-8945

Proposed Plugging Method: Clean well to TD and pump full of cement from btm to top.

Plugging Proposal Received By: ALAN DUNNING

WitnessType: NONE

Date/Time Plugging Completed: 12/03/2010 5:00 PM

KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A 1" cement string was washed to 145' outside the production string. The drill rig was moved to location and the well drilled to 500' inside the production string. The drill pipe was removed and the well perforated at 450' and 250'. A 1" cement string was then lowered to 500' inside the production string. A 2nd 1" string was lowered down the outside of the production pipe to 85'. The well was then pumped full of cement thru these cement strings. A total of 52 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

RECEIVED

FEB 22 2011 *AMD*

KCC Chanute Dist. #3

RECEIVED

FEB 22 2011

KCC WICHITA

Remarks: CONTROL # 20110002-016 THIS WELL WAS GPS'D AS STO-16

Plugged through: CSG

District: 03

Signed

Alan Dunning
(TECHNICIAN)