

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-10322-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 26-33S-43W
2988 feet from S Section Line, 2371 feet from E Section Line
Lease Name: SANTA FE A Well #: 1
County: MORTON Total Vertical Depth: 3255 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	600		WITH 300 SX CMT
PROD	5.5	3254	664	WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/14/2011 11:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT AT 2920'. PLUG AT 1500' WITH 25 SX CMT. PLUG AT 630' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: PARTIAL
Date/Time Plugging Completed: 01/17/2011 5:00 PM KCC Agent: JACK MACCLASKEY

Actual Plugging Report:

3143-3199' PERFS WERE SQUEEZED OFF.1/14/11: PUMP 300# HULLS & 25 SX CMT AT 2920'. SHUT IN 2 HOURS. TAGGED TOC @ 3061'. PUMPED 300# HULLS & 25 SX CMT. SDFW. 1/17/11: TAGGED TOC @ 2362', RELEASE PACKER & CIRCUALTE HOLE WITH MUD, 25 SX CMT @ 1500'. POOH W/TBG & PACKER. SHOOT 5 1/2" CASING AT 664'. PLUG AT 630' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3143	3199		LANSING - SQUEE
3014	3037		TOPEKA
2920	2980		TOPEKA

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: TBG

District: 01

Signed

Jack Macclashky
(TECHNICIAN)

RECEIVED
FEB 10 2011
KCC DODGE CITY

RECEIVED
FEB 17 2011
02-17-11
KCC/WICHITA

FORM P-273