

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-135-24325-00-00  
Spot: SWNESENW Sec/Twnshp/Rge: 34-19S-24W  
1824 feet from N Section Line, 2179 feet from W Section Line  
Lease Name: CAMBRON PM Well #: 1-34  
County: NESS Total Vertical Depth: 4385 feet

Operator License No.: 5086  
Op Name: PINTAIL PETROLEUM, LTD.  
Address: 225 N MARKET STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	280		WITH 180 SX CMT
PC		1614		
PROD	5.5	4376	0	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/07/2011 9:00 AM  
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC  
Proposal Rcvd. from: BILLY BRINEY Company: WHITETAIL CRUDE, INC Phone: (785) 798-3641

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 10 SX GEL & 40 SX CMT WITH HULLS. PULL TBG TO 1600' & CIRCULATE CMT. PULL TBG & TOP OFF. CHECK BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/07/2011 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4300' & PUMP 10 SX GEL & 40 SX CMT WITH 150# HULLS. PULL TBG TO 1600' & PUMP 150 SX CMT. CMT CIRCULATED. PULLED TBG & TOP OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMP 5 SX CMT. PRESSURED TO 500# & HELD.

Perfs:

Top	Bot	Thru	Comments
4376	4385		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed

*Michael Maier*

(TECHNICIAN)

RECEIVED

FEB 10 2011

KCC DODGE CITY

RECEIVED

FEB 23 2011

KCC WICHITA

Form CP-201