

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-20813-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 23-24S-16W  
331 feet from N Section Line, 2283 feet from E Section Line  
Lease Name: PAUL MEYER Well #: 2  
County: EDWARDS Total Vertical Depth: 4160 feet

Operator License No.: 5893  
Op Name: PRATT WELL SERVICE, INC.  
Address: PO BOX 847  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3750		WITH 2 SX CMT
SURF	8.625	490		WITH 300 SX CMT
PROD	5.5	4151	2485	WITH 300 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/11/2011 10:00 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 770-0995

Proposed Plugging Method: SET CIBP @ 3700' & PUT 2 SX CMT ON TOP OF CIBP. PLUG AT 1050' WITH 50 SX CMT. PLUG AT 540' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/11/2011 1:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD: 3980'. SET CIBP @ 3750' & PUT 2 SX CMT ON TOP OF CIBP. 1ST PLUG AT 1050' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 520' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3992	3998		
3774	3793		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed \_\_\_\_\_

*Stephen J. Pfeifer*  
(TECHNICIAN)

RECEIVED  
FEB 17 2011  
KCC DODGE CITY

RECEIVED

FEB 17 2011  
02-17-11  
KCC WICHITA

Form CP-23