

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-147-30001-00-02  
Spot: N2N2SW Sec/Twnshp/Rge: 35-4S-20W  
2186 feet from S Section Line, 3987 feet from E Section Line  
Lease Name: STEPHENS Well #: 2  
County: PHILLIPS Total Vertical Depth: 3270 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 S ST FRANCIS PO BOX 2757  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	202	0	w/150 sxs cmt
T1	2.375	2856		
L1	3.5	2872		
PKR		2856		
PROD	4.5	3300	0	w/150 sxs cmt

Well Type: EOR UIC Docket No: E13887.1 Date/Time to Plug: 01/24/2011 9:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL COMPANY Phone: (785) 259-1928

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 300# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 01/24/2011 2:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 2901' - pumped 38 sxs 60/40 pozmix - 4% gel.  
Pulled tubing to 1903' - pumped 38 sxs 60/40 pozmix - 4% gel.  
Pulled tubing to 905' - pumped 38 sxs 60/40 pozmix - 4% gel.  
Pulled all tubing. Hooked to 3 1/2" liner and pumped 96 sxs 60/40 pozmix - 4% gel with 300# hulls.  
S.I.P. 200#.  
Hooked to 8 5/8" x 4 1/2" annulus. Pumped 40 sxs 60/40 pozmix - 4% gel.  
S.I.P. 75#

Perfs:

RECEIVED  
FEB 04 2011  
KCC WICHITA

Remarks: SWIFT SERVICES, INC.-TICKET #19518.

Plugged through: TBG

District: 04

Signed

Pat Bedore  
(TECHNICIAN)

CM