

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-14857-00-00  
Spot: W2SESE Sec/Twnshp/Rge: 5-19S-11W  
660 feet from S Section Line, 990 feet from E Section Line  
Lease Name: SCHLOCTERMEIER Well #: 3  
County: BARTON Total Vertical Depth: 3391 feet

Operator License No.: 7383  
Op Name: GRADY BOLDING CORPORATION  
Address: PO BOX 486  
ELLINWOOD, KS 67526

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	198	0	250 SX
PROD	5.5	3362	0	150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/14/2011 9:00 AM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: GRADY BOLDING Company: GRADY BOLDING CORPORATION Phone: (620) 564-2240

Proposed Plugging Method: Ordered 400 sxs 60/0 pozmix - 4% gel - 500# hulls - 9 sxs gel.

Plugging Proposal Received By: BRUCE RODIE Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/14/2011 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 1450' - 625' - 175'.  
Ran tubing to 3180' - tied to tubing and pumped 9 sxs gel - followed with 75 sxs cement with 100# hulls.  
Pulled tubing to 1500' - pumped 90 sxs cement with 200# hulls.  
Pulled 650' - pumped 125 sxs cement with 200# hulls - circulated cement to surface on casing.  
Pulled tubing - tied to casing - circulated cement to surface on backside with 30 sxs cement.  
Shut in backside and squeezed to 300# P.S.I. S.I.P. 200#.

Perfs:

Top	Bot	Thru	Comments
3305	3310		
3296	3302		
3248	3259		
3183	3192		
3173	3180		
3155	3158		
3133	3140		
3103	3112		
3082	3087		

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

RECEIVED

FEB 22 2011

Form CP-2/3

FEB 17 2011

KCC WICHITA