

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-20846-00-01
Spot: SENWSENW Sec/Twnshp/Rge: 5-24S-21W
3624 feet from S Section Line, 3422 feet from E Section Line
Lease Name: VIRGINIA GLEASON Well #: 3
County: HODGEMAN Total Vertical Depth: 1490 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	619		WITH 250 SX CMT
PROD	5.5	1490	0	WITH 335 SX CMT

Well Type: SWD UIC Docket No: D20313.0 Date/Time to Plug: 02/04/2011 2:00 PM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: CHARLES R. RAMSEY Company: H & C OPERATING Phone: (785) 434-7434

Proposed Plugging Method: PUMP 500# HULLS, CMT TOP TO BOTTOM. CHECK BACKSIDE WITH 50 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2011 3:01 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

PUMPED 500# HULLS & 115 SX CMT DOWN 5 1/2". MAXIMUM PRESSURE 800 PSIG.
INITIAL SHUT IN PRESSURE 500 PSIG. VISUALLY CHECKED 8 5/8" X 5 1/2"
ANNULUS, HEAD IS COMPLETELY FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
920	1015		Cedar Hills

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

Richard W. Lacey

(TECHNICIAN)

RECEIVED
FEB 23 2011
KCC WICHITA

RECEIVED

FEB 14 2011

KCC DODGE CITY

Form CP-2/3