

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-083-20996-00-00
Spot: NWNESWSW Sec/Twnshp/Rge: 5-24S-21W
1243 feet from S Section Line, 4322 feet from E Section Line
Lease Name: GLEASON VIRGINIA Well #: 4
County: HODGEMAN Total Vertical Depth: 4800 feet

Operator License No.: 8914
Op Name: H & C OIL OPERATING INC.
Address: PO BOX 86
PLAINVILLE, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4714		
SURF	8.625	1208		WITH 475 SX CMT
PROD	5.5	4799	1975	WITH 150 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/04/2011 3:30 PM
Plug Co. License No.: 33645 Plug Co. Name: H2 PLAINS, LLC
Proposal Rcvd. from: CHARLES R. RAMSAY Company: H & C OPERATING Phone: (785) 434-7434

Proposed Plugging Method: SET CIBP @ 4365' & 2 SX CMT. PLUG AT 1230' WITH 15 SX GEL & 50 SX CMT. PLUG AT 600' WITH 50 SX CMT. PLUG AT 40' WITH 15' SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/04/2011 5:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4365' WITH 2 SX CMT ON TOP WITH A DUMP BAILER. 1ST PLUG AT 1230' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 600' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4509	4604		Cherokec
4448	4458		Marmaton
4416	4426		Marmaton

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

Richard M. Lacey

(TECHNICIAN)

RECEIVED
FEB 23 2011
KCC WICHITA

RECEIVED

FEB 14 2011

KCC DODGE CITY

FORM CP-2/3