

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-20893-00-00
Spot: E2NWNW Sec/Twnshp/Rge: 23-34S-26W
4620 feet from S Section Line, 4155 feet from E Section Line
Lease Name: GOODNIGHT Well #: 1-23
County: MEADE Total Vertical Depth: 6115 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5401		WITH 2 SX CMT
SURF	8.625	882		WITH 150 SX CMT
PROD	5.5	6113	3000	WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/27/2011 10:00 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: GEORGE PAYNE Company: JHERMAN L LOEB LLC Phone: (618) 943-2227

Proposed Plugging Method: SET ICBP @ 5815 WITH 2 SX CMT. PLUG AT 1340' WITH 15 SX GEL & 50 SX CMT. PLUG AT 910' WITH 50 SX CMT. PLUG AT 400' WITH 30 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2011 11:30 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

COULD NOT GET BELOW 5418' WITH DUMP BAILER. CIBP @ 5401' WITH 2 SX CMT. 1ST PLUG AT 1340' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 910' WITH 50 SX CMT. 3RD PLUG AT 400' WITH 30 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT. CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5865	5872		Morrow

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL.

Plugged through: TBG

District: 01

Signed

Jerry W. Stapleton
(TECHNICIAN)

RECEIVED
FEB 10 2011
KCC DODGE CITY

RECEIVED
FEB 15 2011
KCC WICHITA