

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21547-00-00
Spot: SWNWSW Sec/Twnshp/Rge: 25-15S-14W
1649 feet from S Section Line, 4979 feet from E Section Line
Lease Name: DIETZ Well #: 2
County: RUSSELL Total Vertical Depth: 3336 feet

Operator License No.: 33813
Op Name: JASON OIL COMPANY, LLC
Address: 3718- 83RD ST PO BOX 701
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	259	0	170 SX
PROD	5.5	3332	0	175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/11/2011 10:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: DAVID FUNK Company: JASON OIL COMPANY, LLC Phone: (785) 324-0643

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 400# hulls - 9 sxs gel.
Perf: 1650' - 880' - 400'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/11/2011 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 3000' - pumped 9 sxs gel - followed with 90 sxs cement with 200# hulls.
Pulled tubing to 1700' - pumped 90 sxs cement with 200# hulls.
Pulled tubing to 880' - pumped 65 sxs cement - cement circulated.
POOH. Hooked to Braden head.
Max. P.S.I. 450#.
Topped off casing with 5 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3332	3336		ARBUCKLE

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #4810.

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

RECEIVED
FEB 17 2011
02-17-11
KCC WICHITA