

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-079-20213-00-01
Spot: NENENW Sec/Twnshp/Rge: 35-22S-2W
4723 feet from S Section Line, 3224 feet from E Section Line
Lease Name: BONJOUR BATES Well #: 1
County: HARVEY Total Vertical Depth: 2995 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N MARKET STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	236		175 SX
PROD	4.5	2994		125 SX

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 12/27/2010 10:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: TRAVIS HAMM Company: _____ Phone: (316) 263-5785

Proposed Plugging Method: AS PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed: 12/28/2010 4:30 PM KCC Agent: SHANE JONES

Actual Plugging Report:

12/27/10 AMERICAN ENERGIES TAGGED SAND @ 2892 AND CAPPED W/4SX. THEY RAN TUBING DOWN THE 4.5" TO 400' AND RAN 1" DOWN THE BACKSIDE TO 400'. COPELAND TIED ON AND CIRCULATED 85 SXS FROM 400' TO SURFACE ON THE BACKSIDE. THEY TEN TIED ON AND CIRCULATED 140 SXS FROM 400' TO THE TOP OF THE 4.5". AFTER COPELAND FINISHED PLUGGING THE BONJOUR-BATES #3. THEY DUMPED 25 SXS DRY 60/40 POS W/4% GEL TO TOP OFF WELL. 12/28/10 I CHECKED TOP PLUG FINDING IT DOWN ABOUT 2'. FLUID ON TOP OF PLUG APPEARS TO BE BUBBLING GAS. I SPOKE W/J KLOCK (DIST 2) ABOUT WHAT WAS THE REMEDY TO FIX THIS. HE SUGGESTED TRYING TO TIE ON TO THE CASING AND SQUEEZE SOME CEMENT INTO IT. THEN CHECK AGAIN THURSDAY. IF IT IS STILL BUBBLING GIVE IT A COUPLE OF DAYS TO SEE IF IT WILL HEEL ITS SELF. IF THIS FAILS WILL HAVE TO DRILL OUT TOP PLUG AND REDO IT. I EXPLAINED THIS TO TRAVIS HAMM (AMERICAN ENERGIES). COPELAND BACK OUT AND MIXED UP 10 SXS OF COMMON AND TIED ON TO CASING AND SQUEEZED. LEFT PRESSURE ON OVER NIGHT. ONLY USED 1 SX USED THE REST TO TOP OFF THE #3 WELL. TK #35196 10 SX COMMON. 12/30/10 I CHECKED TOP PLUG. WELL IS NO LONGER BUBBLING TO SURFACE; WELL IS SEALED.

Perfs:

Top	Bot	Thru	Comments
2959	2962	CSG	

Remarks:
Plugged through: TBG

District: 02

Signed [Signature]
(TECHNICIAN)

RECEIVED
JAN 11 2011
KCC WICHITA
1/26/11

JK