

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20076-00-00
Spot: W2W2E2NE Sec/Twnshp/Rge: 27-33S-34W
1320 feet from N Section Line, 1315 feet from E Section Line
Lease Name: GUTTRIDGE Well #: 1-27
County: SEWARD Total Vertical Depth: 2777 feet

Operator License No.: 4549
Op Name: ANADARKO PETROLEUM CORPORATI
Address: PO BOX 1330
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	765		WITH 350 SX CMT
PROD	4.5	2776	0	WITH 450 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/17/2010 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 300# HULLS & 25 SX CMT AT 2630'. PLUG AT 1650' WITH 25 SX CMT. PLUG AT 770'-0' WITH 55 SX CMT. CHECK ANNULUS.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 12/17/2010 2:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 300# HULLS & 25 SX CMT AT 2630'. 1ST PLUG AT 1650' WITH 25 SX CMT.
2ND PLUG AT 770'-0' WITH 55 SX CMT. PUMP 7 SX CMT DOWN 4 1/2" X 8 5/8"
ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2630	2763		CHASE

Remarks: USED COMMON CEMENT BY SARGENTS.

Plugged through: CSG

District: 01

Signed

Jack L. Machuck

(TECHNICIAN)

RECEIVED

JAN 19 2011

KCC DODGE CITY

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

JAN 21 2011

CONSERVATION DIVISION
WICHITA, KS

[Signature]
1/26/11