

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21356-00-00
Spot: SENWSWSE Sec/Twnshp/Rge: 21-14S-19W
936 feet from S Section Line, 2302 feet from E Section Line
Lease Name: KRAUS D Well #: A-1
County: ELLIS Total Vertical Depth: 3822 feet

Operator License No.: 6931
Op Name: BOWMAN OIL COMPANY, A GENERAL
Address: 805 CODELL RD
CODELL, KS 67663

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	208	0	125 SX
DVT		1510		350 SX
PROD	5.5	3818	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/10/2010 9:30 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: DONALD A. BOWMAN Company: BOWMAN OIL COMPANY, A GENE Phone: (785) 434-2286

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 500# hulls - 13 sxs gel.
Drilled from 2350' to 2750' - lost circulation.
DV Tool 1510' w/350 sxs.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2010 12:45 PM KCC Agent: PAT STAAB

Actual Plugging Report:

RIH with tubing to 2700'. Swift Services rigged to tubing and pumped 10 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 2050' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 1000' - pumped 100 sxs cement to circulate mixed with 100# hulls.
Pulled tubing - rigged to 5 1/2" casing with a swedge and pumped 15 sxs cement.
Max. P.S.I. 300#. S.I.P. 300#.
8 5/8" - rigged to and pumped 5 sxs cement.
Max. P.S.I. 200#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
3818	3822		Arbuckle

10/14/11
2011060099

RECEIVED
AUG 11 2010

Remarks: SWIFT SERVICES, INC.

KCC WICHITA

Plugged through: TBG

District: 04

Signed _____

[Signature]
(TECHNICIAN)

CM

