

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21275-00-00
Spot: N2NWSW Sec/Twnshp/Rge: 1-27S-8W
2080 feet from S Section Line, 660 feet from W Section Line
Lease Name: STUCKY C Well #: 4
County: KINGMAN Total Vertical Depth: 3750 feet

Operator License No.: 6139
Op Name: BOYER, JAY C. ESTATE (DECEASED) D
Address: PO BOX 511
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	216		200 SXS CMT
PROD	4.5	3659	2170	125 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/06/2010 8:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKES TESTING & SALVAGE Phone: (620) 938-2943

Proposed Plugging Method: SAND TO 3500' AND CAP WITH 4 SKS OF CMT. RECOVER CASING. 35 SKS 1200', 35 SKS 700, CIRC CMT 265'-0

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 08/06/2010 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 3500', AND CAPPED WITH 4 SKS OF CMT. THE CASING WAS RECOVERED FROM 2170' AND PULLED TO 1222', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO, WAITED 2 HRS AND TAGGED CMT PLUG AT 1000'. SPOTTED 35 SKS CMT AT 710'. PULLED CASING TO 270' AND CIRC CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3562	3572	CSG	


Remarks: COPELAND CMT AND ACID 34795 60/40 4% GEL

Plugged through: CSG

District: 02

RECEIVED

Signed



(TECHNICIAN)

SEP 27 2010

KCC WICHITA

JK