

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21621-00-00
Spot: SWNESW Sec/Twnshp/Rge: 25-29S-7W
1650 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BARNEY Well #: 1
County: KINGMAN Total Vertical Depth: 4210 feet

Operator License No.: 8740
Op Name: BRAMWELL PETROLEUM, INC.
Address: 15183 SW 25TH AVE
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	210		140 SXS CMT
PROD	5.5	4210	2690	150 SXS CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: AND BACK 50' ABOVE THE PERFS AND CAP WITH 5 SKS OF CMT. RECOVER CASING. 35 SKS OF CMT AT 1200', 35 SKS OF CMT AT 700', CIRC CMT FROM 300'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/16/2010 4:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH SAND TO 4050', AND CAPPED WITH 5 SKS OF CMT. THE CASING WAS RECOVERED FROM 2690' AND PULLED TO 1200', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 700', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 300', WHERE CMT WAS CIRCD TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4138	4144	CSG	
4128	4132	CSG	
4110	4120	CSG	

10/14/10
29/1060101

Remarks: QUALITY WELL SERVICE 60/40 4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
AUG 02 2010
KCC WICHITA