

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20107-00-00
Spot: SESE Sec/Twnshp/Rge: 1-30S-7W
660 feet from S Section Line, 660 feet from E Section Line
Lease Name: CONNAUGHTON Well #: 1
County: KINGMAN Total Vertical Depth: 4104 feet

Operator License No.: 8740
Op Name: BRAMWELL PETROLEUM, INC.
Address: 15183 SW 25TH AVE
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	267		200 SXS CMT
PROD	5.5	4102	2600	125 SXS CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/30/2010 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DOUGLAS BRAMWELL Company: BRAMWELL PETRO INC Phone: (620) 532-6019

Proposed Plugging Method: SAND BACK 50 FT ABOVE THE PERFS AND CAP WITH 5 SKS OF CMT. RECOVER CASING. 35 SKS 1200, 35 SKS 700, CIRC CMT FROM 320-0

Plugging Proposal Received By: STEVE VANGIESON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/01/2010 11:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE SANDED BACK TO 3680' AND CAPPED WITH 5 SKS OF CMT. THE CASIG WAS RECOVERED FROM 2600', AND PULLED TO 1200', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 760', WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 320', WHERE CMT WAS CIRCULATED TO SURFACE.. 7-30-2010 TOPPED OFF CMT 10 YEAR TA.

Perfs:

Top	Bot	Thru	Comments
4084	4096	CSG	


10/14/11
2011060109

RECEIVED
AUG 02 2010
KCC WICHITA

Remarks: QUALITY WELL SERVICE. COMMON 4% GEL

Plugged through: CSG

District: 02

Signed 
(TECHNICIAN)

JK