

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00506-00-01
Spot: NENENE Sec/Twnshp/Rge: 11-30S-7W
4950 feet from S Section Line, 330 feet from E Section Line
Lease Name: MARK OWWO Well #: 2
County: KINGMAN Total Vertical Depth: 4196 feet

Operator License No.: 8740
Op Name: BRAMWELL PETROLEUM, INC.
Address: 15183 SW 25TH AVE
SPIVEY, KS 67142

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	215		175 SX
PROD	4.5	4196		110 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/21/2010 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 727-3410

Proposed Plugging Method: SAND BACK THE PERFS TO 4090' AND CAP WITH 4 SKS OF CMT. RECOVER PIPE. SPOT 35 SKS AT 1200', 35 SKS 700', CIRC CMT FROM 300'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 07/19/2010 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

THE PERFS WERE COVERED WITH AND TO 4090' AND CAPPED WITH 4 SKS OF CMT. NO STRETCH IN 4.5 CASING. PERFORATED 4.5 AT 1200', RAN TUBING AND SPOTTED 35 SKS OF CMT. PERFORATED CASING AT 700', SPOTTED 35 SKS OF CMT. NO CIRCULATION. TAGGED CMT PLUG AT 850'. RAN TUBING BACK TO 700' SPOTTED 35 SKS OF CMT. FLUID CIRCULATED. PERFORATED CASING AT 300'. PUMPED CEMENT DOWN 4.5, CMT FELL AFTER CIRCULATION. LET SET AND TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
4140	4150	CSG	MISSISSIPPI

10/14/11
2011060101


RECEIVED
AUG 02 2010

Remarks: QUALITY WELL SERVICE 60/40 4% GEL

Plugged through: TBC

KCC WICHITA

District: 02

Signed 
(TECHNICIAN)

JK