

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23679-00-00

Spot: N2NESE

Sec/Twnshp/Rge: 26-10S-24W

2310 feet from S Section Line, 660 feet from E Section Line

Lease Name: GEYER

Well #: 1-26

County: GRAHAM

Total Vertical Depth: 4000 feet

Operator License No.: 31160

Op Name: PHILLIPS EXPLORATION COMPANY L.

Address: 1601 SAGEBRUSH
WICHITA, KS 67230

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		

Well Type: DH

UIC Docket No:

Date/Time to Plug: 11/08/2010 9:00 PM

Plug Co. License No.: 30606

Plug Co. Name: MURFIN DRILLING CO., INC.

Proposal Rcvd. from: ANDY DINKEL

Company: MURFIN DRILLING CO., INC.

Phone: (316) 267-3241

Proposed Plugging Method: Ordered 220 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT BEDORE

WitnessType: NONE

Date/Time Plugging Completed: 11/08/2010 11:00 PM

KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

1st. Plug at 2000' w/25 sxs.
2nd. Plug at 1150' w/100 sxs.
3rd. Plug at 270' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.
Mousehole with 15 sxs.

Remarks: QUALITY OIL WELL CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Pat Bedore
(TECHNICIAN)

CM

RECEIVED
Form CP-2/3
NOV 17 2010

NOV 12 2010

KCC WICHITA