

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-19422-00-00  
Spot: NWSESE Sec/Twnshp/Rge: 21-33S-4E  
997 feet from S Section Line, 689 feet from E Section Line  
Lease Name: MURET Well #: 1-A  
County: COWLEY Total Vertical Depth: 3214 feet

Operator License No.: 4699  
Op Name: PHILLIPS OIL PROPERTIES INC.  
Address: 1822 S MEAD  
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	135		165 SX
PROD	4.5	3214		175 SX

Well Type: SWD UIC Docket No: D25693.0 Date/Time to Plug: 08/12/2010 8:00 AM  
Plug Co. License No.: 31539 Plug Co. Name: SAMS WELL SERVICE, INC.  
Proposal Rcvd. from: TROY PHILLIPS Company: PHILLIPS OIL PROPERTIES INC Phone: (316) 265-7779

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/12/2010 1:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG AND CIRCULATING DOWN @ 1609', CONSOLIDATED OIL WELL SERVICES ESTABLISHED CIRCULATION & PUMPED 50 SXS 60/40 POZMIX 4% GEL 3% CC AND DISPLACED IN CASING. TAGGED CEMENT @ 1556'. PRESSURED CASING, HELD OK. RIH W/TBG @ 286', CONSOLIDATED ESTABLISHED CIRCULATION & PUMPED 41 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 8-12-2010, @ 1:00 PM. CONSOLIDATED CEMENT TICKET #28419.

Perfs:


Top	Bot	Thru	Comments
2524	2564	CSG	LAYTON

Remarks:

Plugged through: TBG

District: 02

Signed

  
(TECHNICIAN)

RECEIVED

OCT 28 2010

KCC WICHITA

Form CP-2/3

