

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-00015-00-02  
Spot: SWSWSW Sec/Twnshp/Rge: 33-1S-32W  
332 feet from S Section Line, 4987 feet from E Section Line  
Lease Name: J W KOMPUS A Well #: 4 SWD  
County: RAWLINS Total Vertical Depth: 4641 feet

Operator License No.: 3602  
Op Name: PHILPOTT OIL & GAS CO INC  
Address: 408 MAIN ST PO BOX 450  
ATWOOD, KS 67730

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	410	0	300 SX
PROD	4.5	2772	0	350 SX

Well Type: SWD UIC Docket No: D19424.0 Date/Time to Plug: 10/13/2010 2:00 PM  
Plug Co. License No.: 3152 Plug Co. Name: POE SERVICING INC  
Proposal Rcvd. from: ROGER PHILPOTT Company: PHILPOTT OIL & GAS INC. Phone: (785) 626-3011

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 4% gel - 600# hulls.  
Plug through casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/13/2010 3:30 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 410' w/300 sxs cement.  
4 1/2" casing at 2772' w/350 sxs cement.  
TD 2800'. PBTD 2473'.  
Connected to 4 1/2" production casing - pumped 200 sxs cement mixed with 600# hulls.  
Max. P.S.I. 450#.  
Connected to 8 5/8" surface casing - pumped 25 sxs cement.

Perfs:

Top	Bot	Thru	Comments
2314	2692		OA
2210	2270		OA

RECEIVED  
OCT 19 2010  
KCC WICHITA

Remarks: CONSOLIDATED OILWELL SERVICES LLC.-TICKET #24,500.

Plugged through: CSG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

Form CP-2/3

OCT 14 2010