

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-00252-00-00
Spot: SWNESW Sec/Twnshp/Rge: 35-30S-9W
1650 feet from S Section Line, 3630 feet from E Section Line
Lease Name: LEE Well #: 1
County: KINGMAN Total Vertical Depth: 4510 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	200		175 SX
PROD	4.5	4503		100 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 09/14/2010 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: DAVID BRADLEY Company: QUALITY WELL SERVICE Phone: (620) 727-3409

Proposed Plugging Method: 25 SKS ON THE PERFS. SQUEEZE HOLES AT 1707', WITH 150 SKS CMT. PERF AT 800 AND SPOT 50 SKS OF CMT. PERF AT 250' AND CIRC CMT TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 09/14/2010 3:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

TUBING WAS RUN TO 4440 WHERE 25 SKS OF CMT AND 200# OF HULLS WAS SPOTTED. A 25 SK PLUG WAS SPOTTED AT 1700', THRU THE TUBING. THE PIPE WAS PERFERED AT 800' AND 250'. TUBING WAS RUN TO 800', WHERE 50 SKS OF CMT WAS SPOTTED. THE CMT CIRCULATED TO SURFACE FROM 800', THE TUBING WAS PULLED FROM THE WELL AND WE TIED ON TO THE CASING AND ATTEMPTED TO CIRCULATE CMT FROM THE TOP. THE WELL PRESSURED UP. CUT OFF THE 4.5' AND THE 8.625 4 FEET BELOW GROUND LEVEL. RAN WIRELINE DOWN THE BACKSIDE AND FOUND CMT AT 125'. RAN 1" TUBING TO 125', AND CIRCULATED CMT TO SURFACE.

Perfs:


Top	Bot	Thru	Comments
4440	4445		
4427	4437		
4414	4424		

Remarks: QUALITY WELL SERVICE 60/40 POZ 4% GEL

Plugged through: TBG

District: 02

Signed _____



(TECHNICIAN)

RECEIVED

SEP 27 2010

KCC WICHITA

Form CP-2/3

JK