

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-22130-00-00
Spot: SWSNWSE Sec/Twnshp/Rge: 27-15S-21W
1586 feet from S Section Line, 1785 feet from E Section Line
Lease Name: JL LAND B Well #: 2
County: TREGO Total Vertical Depth: 4350 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	238	0	150 SX
PROD	4.5	4349	0	150 SX

Well Type: EOR UIC Docket No: E26922.1 Date/Time to Plug: 08/02/2010 2:00 PM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: MIKE FRITZLER Company: PINTAIL PETROLEUM, LTD Phone: (785) 798-3641

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 600# hulls.
DV Tool 1697' w/600 sxs.

Plugging Proposal Received By: MARVIN MILLS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/02/2010 4:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 4200' - pumped 150 sxs cement with 250# hulls.
Pulled tubing to 2185' - pumped 130 sxs cement with 150# hulls - good circulation.
Pulled tubing out - topped off casing with 25 sxs cement - full.
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
4212	4220		

RECEIVED
AUG 06 2010
KCC WICHITA

Remarks: SWIFT CEMENTING COMPANY-TICKET #17995.

Plugged through: TBG

District: 04

Signed *Marvin Mills*
(TECHNICIAN)

CM

STATE: KANSAS COUNTY: TREGO REISSUE 27-15S-21W
FIELD: J & L SE NW SE
OPER: CHARTER PROD 1650 FSL 1650 FEL SEC
WELL: B 2 J & L LAND WELL CLASS: U ELEV: 2341 KB
API: 15-195-22130 STATUS: SERVOG 2332 GR
SPUD: 07/29/93 COMP: 01/17/94
DTD: 4350 LTD: FTD: CHEROKEE PBD: 4322

LOC: 12 1/2 MI S RIGA, KS

IP: COMP 1/17/94, SWTR DISP WELL DISP ZONE - CHEROKEE 4212-4220
NO CORES OR DSTS RPTD

LOG TYPES: DENL, DI, NEUT;

CSGS: 8 5/8 @ 238 W/140 SX, 4 1/2 @ 4349 W/150 SX, DV TOOL @ 1697 W/600; TBG: 2
7/8 @ 4184, PKR @ 4194; DRLG COMP 10/06/93 RIG REL 10/06/93

DSTS: DST # 1 (PAWNEE) 4160-4200, OP 15 MIN, REC: 186 FT OGCWM, 310 FT
OGCMW, 62 FT WTR, IFP 137, FFP 246, NO OTHER PRESS;

PERFS: PERF (CHEROKEE) 4212-4220 W/2 PF, ACID W/750 GALS, 10% HCL,
DRLG COMMENTS: LOG TOPS NOT RPTD

OPER ADD: 224 E DOUGLAS STE 400, WICHITA, KS, 67202 PHONE (316) 264-2808;
CONTR: DUKE DRLG RIG # 4

GEOL: ERNIE MORRISON

WELL ID CHANGES: ELEV CHGD FROM 2332 GR

(OVER)

COPYRIGHT 1994 PETROLEUM INFORMATION CORPORATION

DATE 06/17/94 CARD #00050-KS