

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-00282-00-00
Spot: NESWNE Sec/Twnshp/Rge: 22-14S-12W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: MILLER Well #: 3
County: RUSSELL Total Vertical Depth: 3218 feet

Operator License No.: 5086
Op Name: PINTAIL PETROLEUM, LTD.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	217	0	150 SX
PROD	5.5	3212	0	100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/13/2010 9:30 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: BILLY FRITZLER Company: PINTAIL PETROLEUM, LTD. Phone: (316) 263-2243

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 500# hulls - 6 sxs gel.
Perf: 1300' - 550' - 260'.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2010 2:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Ran tubing to 2700' - pumped 6 sxs gel - followed with 75 sxs cement with 200# hulls.
Pulled tubing 1350' - pumped 150 sxs cement with 100# hulls - cement circulated.
POOH. Hooked to Braden head and pumped 10 sxs cement.
Max. P.S.I. 150#.
Hooked up to casing and pumped 15 sxs cement.
Max. P.S.I. 200#.

Perfs:

Remarks: SWIFT CEMENTING COMPANY-TICKET#18203.

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

RECEIVED
AUG 18 2010
KCC WICHITA

Form CP-2/3

AUG 16 2010

LOUIS MAI

#3 MILLER

22-14-12W
NE SW NE

Contr. MAST DRILLING

RUSSELL County

E 1746RB Comm.

Comp


9-30-55 IP 25 BOPD

Tops	Depth	Datum
KC	2870	-1124
B/KC	3113	-1367
CONG	3185	-1439
ARB	3210	-1464
TD	3218	-1472

Casing
5" 3212

CO 3218: AGID 500: 3 BOPD

HALL GURNEY POOL



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS