

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-20815-00-00

Spot: W2SWNE

Sec/Twnshp/Rge: 22-14S-12W

3300 feet from S Section Line, 2310 feet from E Section Line

Lease Name: MILLER

Well #: 8

County: RUSSELL

Total Vertical Depth: 3250 feet

Operator License No.: 5086

Op Name: PINTAIL PETROLEUM, LTD.

Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	657	0	150 sxs cmt
PROD	5.5	3249	1446	125 sxs cmt

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 08/12/2010 10:30 AM

Plug Co. License No.: 31627

Plug Co. Name: WHITETAIL CRUDE, INC

Proposal Rcvd. from: BILLY FRITZLER

Company: PINTAIL PETROLEUM, LTD.

Phone: (316) 263-2243

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 600# hulls.
Sanded off open hole and 5 sxs cement on top.

Plugging Proposal Received By: BRUCE BASYE

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 08/12/2010 2:30 PM

KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Cut casing at 1446'.
Pulled casing to 1350' - pumped 100 sxs cement with 300# hulls.
Pulled casing to 600' - pumped 75 sxs cement with 100# hulls.
Pulled casing to 250' - pumped 110 sxs cement - cement circulated.
POOH. Topped off well with 25 sxs cement.
08/13/2010 - checked fill up 8' down.

Remarks: SWIFT CEMENTING COMPANY-TICKET #18239.

Plugged through: CSG

District: 04

Signed

Ray A. Dinkel


(TECHNICIAN)

CM

RECEIVED
AUG 16 2010
KCC WICHITA

AUG 16 2010

ICER ADDIS #8 MILLER 22-14-12W
 DRAWER 8038, WICHITA, KS. W/2 SW NE
 CONTR DUKE ORLG. CO. CTY RUSSELL
 GEOL DICK FOLEY FIELD CRABTREE
 E 1776 KB 12/3/75 CARD ISSUED 2/19/76 IP P 25 BOPD N/W
 API 15-167-20,815 ARB 3249-50 $\frac{1}{2}$



SMP	TOPS	DEPTH	DATUM
ANH		643	+1133
TOP		2530	- 754
HEEB		2808	-1032
TOR		2828	-1052
DOUG		2840	-1064
BR LM		2893	-1117
LANS		2902	-1126
BKC		3166	-1390
CONG		3205	-1429
ARB		3247	-1471
RTD		3250 $\frac{1}{2}$	-1474 $\frac{1}{2}$

8 5/8" 657/150sx, 5 $\frac{1}{2}$ " 3249/125sx
 DST (1) 2896-2920/1', 150' M W/SP O,
 SIP 1357-1263#/30", FP 63-63#,
 106-106#
 DST (2) 2916-2950/1', 120' MW, SIP 719-
 688#/30", FP 32-43#, 53-74#
 DST (3) 3175-3220/1', 10' OIL SP M,
 SIP 138-92#, FP 36-36#
 DST (4) 3197-3250 $\frac{1}{2}$ /PKR FAILED
 DST (5) 3164-3250/30-30-60-45, 90' OCM,
 60' HOCM, 120' VHOCM, 300' BLK V M
 OIL EMUL, SIP 1061-943#, FP 64-
 166#, 184-341#
 MICT - CO TD, POP

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS