

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-093-20547-00-00
Spot: NW Sec/Twnshp/Rge: 2-23S-38W
4016 feet from S Section Line, 3962 feet from E Section Line
Lease Name: MATHES-HARTMAN Well #: 1
County: KEARNY Total Vertical Depth: 3010 feet

Operator License No.: 6067

Op Name: PRAIRIE ENERGY LC

Address: 1240 GLENBROOK DR
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2000		WITH 2 SX CMT
SURF	8.625	332		
PROD	5.5	3010	0	TOC @ 850'

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 07/01/2010 2:00 PM

Plug Co. License No.: 34082

Plug Co. Name: ALLIANCE WELL SERVICE INC.

Proposal Rcvd. from: BARRY WALTERS

Company: ALLIANCE WELL SERVICE INC.

Phone: (785) 623-1066

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: STEVE DURRANT

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 07/02/2010 11:00 AM

KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG SET CIBP @ 2000' WITH 2 SX CMT. TEST CASING TO 840#. 2ND PLUG PERFORATE 4 HOLES @ 812'. ESTABLISH RATE 1 1/2 BPM @ 550#. 3RD PLUG PUMP 80 SX CMT, 8 BALL SEALERS, & 45 SX CMT. SHUT IN PRESSURE 1000#. 4TH PLUG PUMP 150 SX CMT DOWN ANNULUS. PRESSURE TO 200#.

Perfs:

Top	Bot	Thru	Comments
2865	2935		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

Ken Jehlik
(TECHNICIAN)

RECEIVED

JUL 13 2010

KCC DODGE CITY

RECEIVED
JUL 23 2010

KCC WICHITA

Form CP-278