

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-003-01942-00-00
Spot: NESWSENE Sec/Twnshp/Rge: 14-21S-20E
3158 feet from S Section Line, 752 feet from E Section Line
Lease Name: WEST VAN WINKLE Well #: T-34X
County: ANDERSON Total Vertical Depth: 651 feet

Operator License No.: 34170
Op Name: SIRIUS ENERGY CORP.
Address: 526 COUNTRY PL, SOUTH
ABILENE, TX 79606

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	12	20		
PROD	2	660		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/18/2010 8:00 AM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: RANDY TETER Company: _____ Phone: (785) 448-8571

Proposed Plugging Method: RUN 3/4 INCH PIPE APPROX. 650 FEET AND FILL 2 INCH PIPE WITH APPROX. 20 SACKS. RUN 1 INCH PIPE TO BOTTOM AND FILL BACKSIDE TO SURFACE WITH APPROX. 100 SACKS.

Plugging Proposal Received By: LEVI SHORT WitnessType: PARTIAL
Date/Time Plugging Completed 11/18/2010 12:00 PM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 3/4 INCH INSIDE 2 INCH CASING TO 651 FEET AND FILL WITH 12 SACKS OF PORTLAND CEMENT TO SURFACE. RUN 1 INCH OUTSIDE TO BOTTOM AND PUMP 108 SACKS OF CEMENT. PULL PIPE AND TOP OFF WELL. PUMP TOTAL OF 120 SACKS OF CEMENT.

Perfs:

RECEIVED

JAN 24 2011

LS

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

RECEIVED

JAN 31 2011

KCC WICHITA

Form CP-2/3